

Date: 11-01-2019

BFSL is Inviting Bids from Reputed organisations, channel partners and with same business line for UPS with transformers and Racks for IT device usage.

Site Address:- 3rd Floor, Hallmark Business Plaza, Gurunanak, BARC Hospital Rd, Bandra East, Mumbai, Maharashtra 400085

Terms & Conditions:

- 1) Product should be delivered at site address.
- 2) Bidders can opt to quote for only 1 category as per business line or both the category, bidders will be finalised on commercial basis.
- 3) Payment terms will be 15 days from the date of delivery.
- 4) UPS back up required will be min 30 mins.
- 5) Warranty period and AMC after warranty must be mentioned clearly.
- 6) Kindly provide the make and model of the UPS.
- 7) Delivery timeline to be mentioned.
- 8) Quantity might increase or decrease as per project requirement, but the rates shared by bidders will be the same.
- 9) Any additional cost for the below requirement must be mentioned separately.
- 10) Kindly drop an email to rfp@bobfinancial.com for any clarity or confirmation.
- 11) Sealed quoted to be sent within the stipulated time mentioned at the below address:

Office address:- AVP Procurement - 2nd Floor, Baroda House, Behind Dewan Shopping Centre, S V Road, Jogeshwari (W), Mumbai – 400 102. Landline - [022 42068566](tel:02242068566).

BID Start Date:- 11-01-2019 and **BID END DATE :-** 18-01-2019 by 4:00pm

Below are the Specifications for UPS:

Description	Qty	Unit price	Total cost	AMC cost after warranty	AMC cost after warranty 2nd year
Supply, installation, testing and commissioning of 20kVA UPS, 3 Phase input / output including HRC Fuse / MCCB Protection, IGBT based rectifier & inverter, having < 3% I THD & Input Power factor > 0.98, efficiency @ 100% load > 92%, potential free contacts, including 30 Minutes battery backup with standard accessories, Floor mounting stand & Hardware as completed.	2				
Total Cost After Tax					

Below are the Specifications for Racks:

Sr. No	Description	Qty	Unit price	Total cost
1	42U(800W X 800D)MM Floor Mount Closed Rack with Front Glass Door, Fan Tray on Top, Perforated rear Doors, Keyboard Tray with Shelf, Casters & Open able Entry at the Bottom for the cable 2 Nos. Vertical Power Strip with Standard Accessories.	1		
2	42U(800W X 1200D)MM Floor Mount Closed Rack with Front Glass Door, Fan Tray on Top, Perforated rear Doors, Keyboard Tray with Shelf, Casters & Open able Entry at the Bottom for the cable 2 Nos. Vertical Power Strip with Standard Accessories.	1		
3	24 Port Unloaded patch Panel	15		
4	CAT 6 IO	700		
5	Face Plate	225		
	Total Cost			
	Tax			
	Total Cost with Tax			

Kindly share you're costing for the above requirement.

Thank you,

BFSL